

Express Welding

614 Brixey Road  
 Henrietta, TX 76365  
 (940) 895-3595  
 Fax (940) 895-3596

# Estimate

Date	Estimate #
4/22/2014	352

Name / Address
Clay County Sheriff Dept. 215 W Gilbert St. Henrietta, Tx 76365

			Project
Description	Qty	Cost	Total
Build enclosed fenced area across south side of jail. Fence to be 6' tall mounted on top of stem wall with approx. 5' cantilever over to building but not attaching to building. Enclose with fence on east end and install 4'x8' gate on west end with standard lockable latch. Materials to be used post 1 7/8 scd. 40 top rail and mid rail 1 5/8 scd 40 wire 9 ga.		0.00	0.00
material		2,353.00	2,353.00
labor		2,000.00	2,000.00
total \$4353.00			
<b>Total</b>			<b>\$4,353.00</b>

# PARK FENCE

Kevin Francis

1917 6th Street

Wichita Falls, Texas  
76301

940-642-9559

## PROPOSAL

Date 4/23/14

JOB : Clay County Sheriff.  
Henrietta, Texas

This bid is for all Labor and materials.

This bid will be for the construction of 71' of chain Link fence with a chain link top. Fence will be mounted on retaining wall. Actual chain link fabric height will be 7' off retaining wall. There will be seven post attached to cement adjacent to post set on retaining wall. This will be for the construction of the chain link top which will run the complete length of the fence. Fence will have one walk thru gate. Post on retaining wall will be welded to existing sleeves or plated were sleeve is not available. Post on ground next to the jail house will be plated.

Corner post will be... 2 3/8" x sch 40 galvanized  
Line post will be... 2 3/8" x sch 40 galvanized  
All frame work will be 1 5/8" x sch 40 galvanized  
Fabric will 7' x 9 gauge.

Total \$4,250.00

### ACCEPTANCE OF PROPOSAL

DATE \_\_\_\_\_

SIGNATURE \_\_\_\_\_

SIGNATURE \_\_\_\_\_