

EXECUTIVE SUMMARY

PROJECT LAYOUT

The following is a summary of the changes to the project layout between the Exhibit B attached to the Amended and Restated Tax Abatement Agreement between Clay County, Texas (the "County") and Shannon-1 Wind Farm, LLC dated March 14, 2014 which was recorded in Volume 51 at pages 203 et seq. of the Official Public Records of Clay County, Texas the Amended and Restated Tax Abatement Agreement between the County and South Clay Wind Farm, LLC dated March 14, 2014 which was recorded in Volume 51 at pages 201 et seq. of the Official Public Records of Clay County, Texas and the revised project layout attached as Exhibit A to the Supplemental Agreement among the County, Shannon-1 Wind Farm, LLC and South Clay Wind Farm, LLC effective as of December 22, 2014:

- The project area has remained largely unchanged, with the exception of the addition of three (3) tracts of land south of Oliver Road and east of Wright Road and the removal of some tracts of land to avoid existing oil infrastructure.
- The planned access routes to the project area for construction equipment, material delivery and equipment delivery are unchanged.
- The wind turbines selected for the project were updated based on the latest available technology. The primary change is that the turbine rotor diameter (blade sweep area) has been increased from 100m (328 ft) to 103m (338 ft).
- The layout of the rows of wind turbines has been optimized and the final wind turbine locations have been updated within the project area. Wind turbine generators have been moved to avoid existing microwave beam paths.
- The number of wind turbines has increased from 116 to 119 as a result of project optimization.
- The revised site plan shows additional detail of the permanent project infrastructure, including locations of project roads for accessing the turbines, electrical collection and transmission lines, project substation, Oncor interconnection substation, and permanent meteorological towers. The plan also shows the location of temporary construction facilities, including the project laydown and batch plant areas.
- There has also been some consequential renumbering of turbines to reflect updates to layout.