

- PCT. 1- ALTERNATE
- PCT. 2- ALTERNATE
- PCT. 3- ALTERNATE
- PCT. 4- PRIMARY

BID SHEET
Rock (Sand and Gravel)

BIDDER'S COMPANY NAME

P+K Stone, LLC

ADDRESS

PO Box 189

Chico, TX. 76431

PHONE

940-644-1847

LOCATIONS AND SPECIFICATIONS:

BID PRICE PER TON: FOB P+K
Chico Plant

- Precinct No. 1--Byers, Texas
- Precinct No. 2--Dean, Texas
- Precinct No. 3--Midway, Texas
- Precinct No. 4--Bellevue, Texas

1 1/2" Crusher run base A-1 BASE

\$7.00 per ton

1" Crusher run base

Pit run base

Screening 3/8" and down

\$6.00 per ton

3/4" down base

Backfill

\$2.00 per ton

3" Rock (2"x3")

\$12.00 per ton

4" Rock (3"x5") (4"x8")

\$12.00 per ton

Septic Rock

2" - 6" Oversize (8"x12")

\$17.00 per ton

1 1/2" - 3" Small Oversize

Asphalt (hot mix)

Asphalt (coal mix)

Screening

\$6.00 per ton

Base Material 1 1/2"

\$7.00 per ton

Millings

Rejects (Base)

\$ 5.25 per ton

Kerrin Boyd
Authorized Signature

1" utility

\$ 9.25 per ton

1" Washed #57

\$ 14.00 per ton

12" X 18"

\$ 18.00 per ton

18" X 24"

\$ 19.00 per ton

24" X 36"

\$ 21.00 per ton

FLEX BASE ANALYSIS REPORT



Report Number: 95201168.0008
Service Date: 08/03/20
Report Date: 08/19/20 Revision 1 -

2501 E Loop 820 N
Fort Worth, TX 76118-6978
817-268-8600 Reg No: F-3272

Client

P & K Stone LLC
Attn: Kevin Boyd
PO Box 189
Chico, TX 76431

Project

P&K Stone - Aggregate Testing
2501 E Loop 820 North
Fort Worth, TX 76118

Project Number: 95201168

Date Sampled: 8/03/2019
Source of Material: Chico Plant
Sample Location: Sample Delivered to Terracon Lab by Client
Material Description: Crushed Limestone
Material Use: Flex Base

Method of Tests: Tex 104-E, 105-E, 106-E, 110-E and 116-E

<u>Sieve Size</u>	<u>Cumulative % Retained</u>	<u>TxDOT Type D, Grade 1-2 Specifications</u>
2 1/2"	0	0
1 3/4"	0	0-10
7/8"	18.2	10-35
3/8"	46.1	30-65
No. 4	59.1	45-75
No. 40	84.4	65-90
Wet Ball Mill Value, %	26	40 max
% Increase	11	20 max
Liquid Limit	23	40 max
Plastic Limit	14	
Plasticity Index	9	10 max

The above aggregate complies with TxDOT Item 247, Type A, Grade 1-2

Services:

Terracon Rep.: Contractor

Reported To:

Contractor:

Report Distribution:

(1) P & K Stone LLC,
kboyd@pkstonellc.com

Reviewed By:

Gregg Albritton

Laboratory Manager

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.