

**SCOPE OF WORK: A1-1**

---

**Break Room, Hallway:**

- (a) Install 5/8 drywall, tape, mud float and texture areas that drywall has been removed.
- (b) Install batt insulation in wall areas where insulation has been removed.
- (c) Paint walls in break room & paint hallway walls at repaired areas only.
- (d) Install custom built ADA vanity cabinet.
- (e) Stain & finish new custom built ADA vanity cabinet.
- (f) Install granite vanity top.
- (g) Re- install vanity sink and sink fixture.
- (h) Install customer supplied rubber base mold & adhesive in break room.
- (i) Contractor agrees to remove construction debris from premises.

Notes: \_\_\_\_\_

---

**COMPANY PROPOSAL**

---

We, Wichita Falls Renovation Group LLC, propose the above scope of work includes labor and material as specified for the amount **\$11,865.00**

Submitted by (Company Representative)

---